



GENERAL NOTES:

1. UNITS ARE SEALED WITH BUTYL TAPE AT THE JOINTS
2. DELIVERY IS MADE BY CRANE-EQUIPPED TRUCKS
3. EXCAVATION MUST BE READY, SAFE AND ACCESSIBLE FOR UNLOADING FROM THE REAR OF THE TRUCK.
4. MIN OVERHEAD CLEARANCE OF 18FT IS REQUIRED
5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT (I.E. SPREADER BAR)
6. SCHEMATIC ONLY (FURTHER DETAIL UPON REQUEST)
7. MAXIMUM BURIAL DEPTH=30"



MANUFACTURED:
OTTAWA, ON
1-800-655-3430

CONCRETE: 35MPa/5000PSI
AIR ENTRAINMENT: 6-8%
MEETS CAN/CSA-B66-00
REINFORCEMENT: MEETS G30.14-M1983

WEIGHT:
TOP: 16,000lbs/7,250kg
BOTTOM: 16,000lbs/7,250kg
CSA APPROVED

DRAWN BY:
S.RIMLAND

DATE:
JAN / 2018

13650 LITRES
3000 IMPERIAL GALLON

SEPTIC TANK

3,000 IMPERIAL GALLON / 13,650 LITRES