



**GENERAL NOTES:**

1. UNITS ARE SEALED WITH BUTYL TAPE AT THE JOINTS
2. DELIVERY IS MADE BY CRANE-EQUIPPED TRUCKS
3. EXCAVATION MUST BE READY FOR INSTALL
4. MIN OVERHEAD CLEARANCE OF 18FT (5.5 METRES) IS REQUIRED
5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT
6. MAXIMUM BURIAL DEPTH = 1 METRE IN FIRM SOIL AWAY FROM ANY VEHICULAR TRAFFIC



MANUFACTURED:  
OTTAWA, ON  
1-800-655-3430

CONCRETE: 40MPa/ 5,800PSI  
AIR ENTRAINMENT: 5-8%  
MEETS CAN/CSA-B66  
REINFORCEMENT: STEEL TO CSA CAN  
A23.1 /A23.3 G30.18 Fy=400MPa

APPROX. TOTAL UNIT WEIGHT:  
32,552lbs / 14,765kg  
CSA APPROVED  
"AGINP"

DRAWN BY:  
N.CHAN

DATE:  
MAR/2021

**14000 LITRES**

WORKING CAPACITY: 13,881L TO INVERT OF OUTLET

TOTAL CAPACITY: 16,451L TO UNDERSIDE OF CHAMBER LID

**SEPTIC TANK**