



**GENERAL NOTES:**

1. UNITS ARE SEALED WITH BUTYL TAPE AT THE JOINTS
2. DELIVERY IS MADE BY CRANE-EQUIPPED TRUCKS
3. EXCAVATION MUST BE READY FOR INSTALL
4. MIN OVERHEAD CLEARANCE OF 18FT (5.5 METRES) IS REQUIRED
5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT
6. MAXIMUM BURIAL DEPTH = 1 METRE IN FIRM SOIL AWAY FROM ANY VEHICULAR TRAFFIC



MANUFACTURED:  
OTTAWA, ON  
1-800-655-3430

CONCRETE: 40MPa at 28 days / 5,800PSI  
AIR ENTRAINMENT: 5-8%  
REINFORCEMENT: STEEL TO CSA CAN  
A23.1 /A23.3 G30.18 Fy=400MPa

APPROX. TOTAL UNIT WEIGHT:  
36,398lbs / 16,509kg  
CSA APPROVED  
"AGINP"

DRAWN BY:  
N.CHAN

DATE:  
MAR/2021

**18000 LITRES SINGLE CHAMBER**

WORKING CAPACITY: 18,658L TO INVERT OF INLET  
TOTAL CAPACITY: 20,492L TO UNDERSIDE OF CHAMBER LID