



**GENERAL NOTES:**

1. UNITS ARE SEALED WITH BUTYL TAPE AT THE JOINTS
2. CONTRACTOR TO ENSURE CRANE IS ON-SITE TO OFFLOAD AND SET TANK
3. EXCAVATION MUST BE READY FOR INSTALL
4. MIN OVERHEAD CLEARANCE OF 18FT IS REQUIRED
5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT
6. MAXIMUM BURIAL DEPTH = 1 METRE IN FIRM SOIL AWAY FROM ANY VEHICULAR TRAFFIC



MANUFACTURED:  
OTTAWA, ON  
1-800-655-3430

CONCRETE: 45MPa / 6,500PSI  
AIR ENTRAINMENT: 6-8%  
MEETS CAN/CSA-B66  
REINFORCEMENT: MEETS G30.14-M1983

CSA APPROVED  
WEIGHT: 48,500lbs / 22,000kg (TOP)  
48,500lbs / 22,000kg (BOTTOM)

DRAWN BY:  
S.RIMLAND

DATE:  
JAN/2019

**45500 LITRES**  
10,000 IMPERIAL GALLON

**SEPTIC TANK**

WORKING CAPACITY: 46,442L TO INVERT OF OUTLET

TOTAL CAPACITY: 48,864L TO UNDERSIDE OF CHAMBER LID