



GENERAL NOTES:

1. UNITS ARE SEALED WITH BUTYL TAPE AT THE JOINTS
2. CONTRACTOR TO ENSURE CRANE IS ON-SITE TO OFFLOAD AND SET TANK
3. EXCAVATION MUST BE READY FOR INSTALL
4. MIN OVERHEAD CLEARANCE OF 18FT IS REQUIRED
5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT
6. MAXIMUM BURIAL DEPTH = 1 METRE IN FIRM SOIL AWAY FROM ANY VEHICULAR TRAFFIC



MANUFACTURED:
OTTAWA, ON
1-800-655-3430

CONCRETE: 45MPa / 6,500PSI
AIR ENTRAINMENT: 6-8%
REINFORCEMENT: MEETS G30.14-M1983

CSA APPROVED
WEIGHT: 46,300lbs / 21,000kg (TOP)
46,300lbs / 21,000kg (BOTTOM)
MEETS CAN/CSA-B66

DRAWN BY:
S.RIMLAND

DATE:
JAN/2019

45500 LITRES SINGLE CHAMBER
10,000 IMPERIAL GALLON

WORKING CAPACITY: 47,367L TO INVERT OF INLET
TOTAL CAPACITY: 48,864L TO UNDERSIDE OF CHAMBER LID