



- GENERAL NOTES:**
1. UNITS ARE SEALED WITH BUTYL TAPE AT THE JOINTS
 2. CONTRACTOR TO ENSURE CRANE IS ON-SITE TO OFFLOAD AND SET TANK
 3. EXCAVATION MUST BE READY FOR INSTALL
 4. MIN OVERHEAD CLEARANCE OF 18FT (5.5 METRES) IS REQUIRED
 5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT
 6. TANK DESIGNED FOR A MAXIMUM FILL COVER DEPTH OF 1000mm, NO MINIMUM FILL COVER DEPTH, AND 12 kPa VEHICLE LOADING.



MANUFACTURED:
OTTAWA, ON
1-800-655-3430

CONCRETE: 40MPa / 5,800PSI
AIR ENTRAINMENT: 5-8%
MEETS CAN/CSA-B66
REINFORCEMENT : MEETS G30.14-M1983 "AGINP"

CSA APPROVED
WEIGHT: 81,065lbs/36,770kg (TOP)
81,625lbs/37,025kg (BOTTOM)

DRAWN BY:
N.CHAN

DATE:
MAR/2021

84000 LITRES **SEPTIC TANK**
WORKING CAPACITY: 84,445L TO INVERT OF OUTLET
TOTAL CAPACITY: 91,455L TO UNDERSIDE OF CHAMBER LID