



- GENERAL NOTES:**
1. UNITS ARE SEALED WITH BUTYL TAPE AT THE JOINTS
  2. CONTRACTOR TO ENSURE CRANE IS ON-SITE TO OFFLOAD AND SET TANK
  3. EXCAVATION MUST BE READY FOR INSTALL
  4. MIN OVERHEAD CLEARANCE OF 18FT (5.5 METRES) IS REQUIRED
  5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT
  6. TANK DESIGNED FOR A MAXIMUM FILL COVER DEPTH OF 1000mm, NO MINIMUM FILL COVER DEPTH, AND 12 kPa VEHICLE LOADING
  7. SAFETY LIDS INSTALLED IN ALL OPENINGS AS PER CSA-B66-21



**MANUFACTURED:**  
OTTAWA, ON  
1-800-655-3430

**CONCRETE:** 40MPa / 5,800PSI  
**AIR ENTRAINMENT:** 5-8%  
**MEETS CAN/CSA-B66**

**CSA APPROVED**  
**WEIGHT:** 81,065lbs/36,770kg (TOP)  
81,625lbs/37,025kg (BOTTOM)

**REINFORCEMENT :** MEETS G30.14-M1983 "AGINP"

**DRAWN BY:**  
JAY PATEL

**DATE:**  
APRIL/2022

**84000 LITRES**

**SEPTIC TANK**

**WORKING CAPACITY:** 84,445L TO INVERT OF OUTLET  
**TOTAL CAPACITY:** 91,455L TO UNDERSIDE OF CHAMBER LID