



- GENERAL NOTES:**
1. UNITS ARE SEALED WITH BUTYL TAPE AT THE JOINTS
 2. CONTRACTOR TO ENSURE CRANE IS ON-SITE TO OFFLOAD AND SET TANK
 3. EXCAVATION MUST BE READY FOR INSTALL
 4. MIN OVERHEAD CLEARANCE OF 18FT (5.5 METRES) IS REQUIRED
 5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT
 6. TANK DESIGNED FOR A MAXIMUM FILL COVER DEPTH OF 1000mm, NO MINIMUM FILL COVER DEPTH, AND 12 kPa VEHICLE LOADING.



MANUFACTURED:
OTTAWA, ON
1-800-655-3430

CONCRETE: 45MPa at 28 days / 6,500PSI **WEIGHT:** 81,065lbs/36,770kg (TOP)
81,625lbs/37,025kg (BOTTOM)
AIR ENTRAINMENT: 5-8%
REINFORCEMENT : STEEL TO CSA
CAN A23.1 /A23.3 G30.18 Fy=400MPa
CPA CERTIFIED
MEETS CAN/CSA-B66
"AGINP"

DRAWN BY:
N.CHAN
DATE:
FEB/2020

86000 LITRES
18900 IMPERIAL GALLON

SEPTIC TANK

WORKING CAPACITY: 83,629L TO INVERT OF OUTLET
TOTAL CAPACITY: 91,455L TO UNDERSIDE OF CHAMBER LID