







GENERAL NOTES:

- 1. DELIVERY IS MADE BY CRANE-EQUIPPED TRUCKS
- 2. EXCAVATION MUST BE READY, SAFE AND ACCESSIBLE FOR UNLOADING FROM THE REAR OF THE TRUCK.
- 3. MIN OVERHEAD CLEARANCE OF 18FT IS REQUIRED
- 4. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT (I.E. SPREADER BAR)



MANUFACTURED: BROOKLIN, ON 1-800-655-3430 CONCRETE: 35MPa / 5,000PSI AIR ENTRAINMENT: 6-8%

REINFORCEMENT: STEEL TO CSA CAN A23.1 / A23.3. G30.18

Fy=400MPa

WEIGHT:

BCP114T9V - 3,130lbs / 1,422kg

DRAWN BY: S.RIMLAND BCP114T9V

DATE: AUG/2017 PRECAST TOP FOR TRANSFORMER FOUNDATION