







## **GENERAL NOTES:**

- 1. DELIVERY IS MADE BY CRANE-EQUIPPED TRUCKS
- 2. EXCAVATION MUST BE READY, SAFE AND ACCESSIBLE FOR UNLOADING FROM THE REAR OF THE TRUCK
- 3. MIN OVERHEAD CLEARANCE OF 18FT IS REQUIRED
- 4. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT (I.E. SPREADER BAR)



MANUFACTURED: BROOKLIN, ON 1-800-655-3430 CONCRETE: 35MPa / 5,000PSI
AIR ENTRAINMENT: 6-8%
REINFORCEMENT: STEEL TO CSA

CAN A23.1 / A23.3. G30.18 Fy=400MPa

**WEIGHT:** BCP330TV - 2,315lbs / 1,050kg DRAWN BY: S.RIMLAND BCP330TV

DATE: AUG/2017 PRECAST TOP FOR TRANSFORMER FOUNDATION