



GENERAL NOTES:

1. CABLE ENTRY OPENINGS - 4-3/4" PVC SEALS
2. DELIVERY IS MADE BY CRANE-EQUIPPED TRUCKS
3. EXCAVATION MUST BE READY, SAFE AND ACCESSIBLE FOR UNLOADING FROM THE REAR OF THE TRUCK.
4. MIN OVERHEAD CLEARANCE OF 18FT IS REQUIRED
5. ALL UNITS MUST BE HANDLED WITH PROPER LIFTING EQUIPMENT (I.E. SPREADER BAR)
6. MAXIMUM BURIAL DEPTH 2084mm EXCAVATION OR 300mm FROM FINISHED GRADE TO TOP OF PRECAST SLAB



MANUFACTURED:
BROOKLIN, ON
1-800-655-3430

CONCRETE: 35MPa / 5,000PSI
AIR ENTRAINMENT: 6-8%
REINFORCEMENT: STEEL TO CSA
CAN A23.1 / A23.3. G30.18 Fy=400MPa

WEIGHT:
LID 9,471lbs / 4,295kgs
TOP 21,285lbs / 9,655kgs
BCP505M - 30,756lbs / 13,950kg

DRAWN BY:
S.RIMLAND

DATE:
AUG/2017

BCP505M

PRECAST CONCRETE UTILITY MANHOLE